

Case Study: Yakutat Energy Efficiency Upgrade

2013 Village Energy Efficiency Program (VEEP)

Buildings Selected



Elementary School



Courthouse

High School



City Offices

Unique Aspects

- 2 schools, wood shop, PSO building, power plant and adjacent residence all use recovered heat (RH) from power plant
- 20-30 year old heat recovery system
- No heat plant backup in schools, wood shop or PSO building
- Insufficient heat for coldest days
- High School at end of RH loop
- Severe design deficiencies
 - No isolation heat exchangers in PSO (forced air and sub-floor) or wood shop (AHU and fintube)
 - Reversed piping to PSO
- 2 decades of deferred maintenance in schools

Existing Conditions

Deferred Maintenance


High School

- was pneumatic; now no controls, no pneumatics
- 1 AHU running backwards
- OSA dampers locked closed
- Relief dampers non-functional
- Local ball valves used to control zone temperatures
- On/off to control ventilation




High School CO2 & Temperatures

Administrative Office; Thursday through Monday



High School CO2 & Temperatures



Deferred Maintenance




Elementary School

- Pneumatic, no controls, severe overheating
- Logged 8 hrs/day pneumatic compressor
- All AHU's running backwards (phase problem)
- Kitchen MAU disabled
- DHW running into cold water, back-feeding lav's & WC's

Elementary School CO2 & Temperatures


Tribal Conference Room (Elem. School Second floor); Wednesday through Friday



Deferred Maintenance

Natatorium


- 100% OSA de-humidification
- 2500 cfm EF removed
- Positive static pressure
- 89.5°F water temp, 88.5°F air temp, 65% RH
- corrosion



Deferred Maintenance



Natatorium CO2 & Temperatures




Proposed Conditions

High School

- Demo remaining pneumatics
- Simple Electronic Controls on 6 AHU's
 - Prestige IAQ Controller
 - JADE Economizer Control
 - Honeywell T755 Analog Output Controller
- Combination of Wi-Fi & standard tstats
- New electronic actuators
- 3-way valves to 2-way
- VFD circulation pumps
- CO2 based demand controlled ventilation
- Re-pipe boiler room, remove boiler

High School




High School

- Correct improper hydronic piping
- Install BTU Monitor
- Fix hydronic leaks
- Replace defective coils & fintube
- Install freezstats and smoke detectors
- Replace missing locker room EF's, add Occupancy sensors
- Replace expansion tank
- Replace hot water generator
- Replace cabinet unit heater

Elementary School

- Demo pneumatics
- Simple Electronic Controls on 3 AHU's (Natatorium AHU eliminated from program), same as High School
- 14 zone Wi-Fi tstats; add Wi-Fi coverage
- 14 new zone valves
- New electronic actuators
- 3-way valves to 2-way
- VFD circulation pumps
- CO2 based demand controlled ventilation

Elementary School



Elementary School

- Occupancy sensors on all EF's
- Install freezstats and smoke detectors
- Repair unit ventilator, replace fintube
- Replace oil fired HWH with HWG
- Install BTU meter
- Remove boiler & piping
- Repair hydronic leaks
- Replace pool circulation pump with premium efficiency
- Replace expansion tank

Wood Shop

- Install isolation heat exchanger
- Replace fintube, add control valves, circulation pumps & controls
- Install BTU meter
- Setback tstats

PSO Building

- Install isolation heat exchanger & hydraulic separator
- Add mixing valve for slab heat & controls
- Install BTU meter
- Setback tstats

Heat Recovery Loop

- Consolidate circulation pumps
- Procure back-up main circulation pump
- Correct reversed piping to PSO building

Courthouse & City Offices

- Setback, Wi-Fi tstats
- Upgrade lighting to LED
- Replace missing bathroom EF's
- Add occupancy sensors on bathroom EF's

Project Development & Management

Project Development

Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun
2013				2014												2015						
Grant Submittal	Grant Awards				Energy Audits				Stakeholder Meetings		Contractor Walk-throughs			CBY Assembly Approval		Construction					Construction completed	

12 months in development phase:

- Energy Audits
- Stakeholder meetings, prioritization of EEM's
- 5% design, contractor walk-through & quotes, asbestos inspection
- Stakeholder meetings, round 2
- Council Approval & contracts

Project Management

Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	
2013					2014												2015						
Grant Submittal	Grant Awards				Energy Audits				Stakeholder Meetings		Contractor Walk-throughs			CBY Assembly Approval		Construction						Construction completed	

7 months in construction phase:

- Construction
- Inspections, (informal) commissioning
- Completed at 99% of budget
- Completed on schedule

Funding

VEEP Program

- \$300,000 VEEP Grant
- \$311,540 Tongass Economic Relief Funds (TERF)


Self Managed

- \$167,000 lighting upgrade (TERF funds):
 - All LED in both schools including fixture by fixture occupancy sensors in high bay gym & multi-purpose
 - Electrical contractor performed data logging and energy savings calculations
 - Completed December 2013


Total EE upgrades \$778,540

Use of Funds

Distribution of costs for \$611,540 funds by building



Distribution of costs by type



Projected Costs, Savings and Payback


Building(s)	Implementation Cost	Savings	Payback (years)
High School, Wood Shop, PPSO building & Waste Heat loop	\$386,804	\$57,177	6.8
Elementary School	\$194,107	\$68,126	2.8
Courthouse	\$20,261	\$2,687	7.5
City Office	\$10,368	\$3,081	3.4
TOTALS	\$611,540	\$131,071	4.7

\$5.26/gallon @ 80% thermal efficiency equivalency for cost of recovered heat

\$.4583/kWh, no PCE for schools

Natatorium upgrades eliminated due to budget limitations

Actual Savings through July 2015



- No heating penalty for lighting upgrade
- No actuals yet for Courthouse & City Office

Open Issues

- 160°F heat loop supply glycol at power plant down to 146°F at High School
- Insufficient recovered heat to maintain High School supply air temperatures when Temp < 25°F
- No backup heat sources
- Aging heat recovery infrastructure
- Declining school enrollment & budget

Conclusions

- This 4-5 year payback is typical
- In rural villages, energy efficiency upgrades are likely to be 80% maintenance and 20% energy efficiency
- Deferred maintenance programs can be “packaged” with energy efficiency upgrades and financed via savings

- Use experienced, bush-proven contractor resources
- Use a general contractor who is using his own proven subs

- Keep the energy auditor involved for design integrity, perform M & V
- Keep solutions simple & appropriate
- Get stakeholders involved early and often, keep them informed, respond to local input



Jim Fowler, PE

jim@jim-fowler.com

907-269-4350

Commercial Municipal and Industrial Energy Audits
Retro-Commissioning
Energy Studies

